### CHP Plant Central Controller Development and Testing with RTDS

TJ)100

TANEL SARNET

JAKO KILTER

Department of Electrical Power Engineering and Mechatronics

Power Systems Research Group

Taltech

10.10.2018

### Agenda

- Power Systems Research Group overview
- RTDS @TalTech
- CHP Central controller
  - Project overview
  - Stage 1: Design of the Central Controller
  - Stage 2: RTDS Model Development & HIL Setup
  - Stage 3: Commissioning test
- Conclusions



### **Power Systems Research Group**

Team of 12 persons (professor, lecturers, researchers, PhD students)

Group leader prof Jako Kilter

Teaching – BSc, MSc	<b>Research and development</b>	Cooperation	
Power system basics	PMUs and wide-area protection and control	Universities (TU Berlin, TU Dresden, Uo Manchester, Aalto, TU Delft,	
Power system stability	Power system inertia monitoring	NTNU)	
Relay protection and automation		Industrial and utility partners in	
Substations	Power quality in transmission Network	Estonia	
Power Quality	Relay protection and system automation	CIGRE (B4, C3, C4)	
	Power generating facility modelling and performance assessment	CIGKL (D4, C3, C4)	

### **RTDS @TalTech**

• 2 x Racks


- 8 x PB5 Processor cards
- 1 x GTNETX2
  - PMU
  - IEC-104
  - GSE/Goose
  - SV (Sampled Values)
- 3 x Omicron CMS 356 amplifiers





### **CHP Central controller: Project overview**

**Objective**: design a common control for Gen 1 and 2 to control them as a single unit at PCC.



### **CHP Central controller: Project overview**

- Central Control (Plant) controller required by TSO requirements for new generators;
- Technical conditions and timeline → **no off-the-shelf solutions**;
- Tight deadlines:


Πυ>100

• Project completed in 30 days.

### π)100

### **CHP Central controller: Design specifications**

- Combined regulation P & Q/U at PCC;
- No measurements from PCC → control based on estimation;
- Accuracy requirements by TSO:
  - P: ± 1 MW
  - Q: ± 1 Mvar
  - U: ± 1 kV




### **CHP Central controller: Technical challenges**

- Different generators: significant regulation and capability differences;
- Gen. -1 parameters fixed;

Πυ>100

 Additional power plant at PCC.




### **Stage 1: Design of the Central Controller**


- Control system design and implementation on PSCAD;
- Developing contractor requested features;
- Approval from TSO


### **Stage 1: Design of the Central Controller**


- Black box PSCAD model of the nearby power plant;
- Cooperation testing requirements:


- No significant impact to nearby generator stability during fault at PCC;
- No reactive power hunting between generators;
- No undamped oscillations due to central control operation.
- Cooperation tests repeated during HIL development.





















### **Central Controller: Reactive Power Control**



18


### πυ 100





### **Central Controller: Limiter Functions**


AUXILIARY BUS VOLTAGE LIMITER



## π)100

### **Central Controller: PCC Bus Voltage Control**

- Controls power plant 110 kV bus voltage;
- PCC voltage control achieved by **voltage drop compensation**.




### Stage 2: RTDS Model Development & HIL Setup

 Developed based on PSCAD model;

- Generator appropriate controls modelled;
- Hardware

   implementation of
   central control system
   developed in parallel
   with RTDS model.



### TUX100 RTDS Model Verification

- Model verification done based on the PSCAD model;
- RTDS model was verified according to:
  - No-load voltage step response;
  - Grid connected voltage reference step response;
  - Active power regulation speed;
  - Reactive power regulation speed;
  - 3-phase fault at PCC (0.25 s);
  - Sudden network impedance change.

### Hardware-in-the-loop: Setup

- Modelling of the power plant IEC-104 communication system;
- Master station (central control system) is SAE IT-systems Net-line FW-50.

# BI:	Binary Input Obje	cts 1,2 in DNP	Specification
BI: 0	PctrlONSW1	PctrlONSW1	0
BI: 1	UctrlONFB	UctrlONFB	0
BI: 2	QctrlONFB	QctrlONFB	0
BI: 3	PrimONFB	PrimONFB	0
BI: 4	Glprimact5	G1primact5	0
BI: 5	Glprimact12	G1primact12	0
BI: 6	GIRPF GIRPF	0	
BI: 7	G1RPact G1RPact	0	
BI: 8	GlcomF GlcomF	0	

### **Electrical** system Control system IEC 104 Master Station PB5 ETHERNET SWITCH Ethernet Cable GTNET

**RTDS signal configuration file** 

### Hardware-in-the-loop: Control System Adjustment

- Control system "converted" from PSCAD to Net-line FW-50;
- Conversion is not 1:1 because of differences in control blocks implementations by the programs:
  - Optimization and workarounds based on HIL simulations.
- Final tuning of the control systems.

### Hardware-in-the-loop: Challenges

- RTDS does not support double point information:
  - Requires significant redesign of state information.

Point information	Status		Point information	Status		
11	closed		1	closed		
01	open		0	open		
00	error	R	<b>RTDS configuration</b>			
Plant configuration						
Translation layer						


### **Stage 3: Commissioning Test**

- Tests to demonstrate the control system performance to the Estonian TSO Elering AS;
- 32 test cases divided in 3 groups:
  - Active power control;
  - Reactive power control;
  - Voltage control.




### **Commissioning Test: Runtime Schematic**

• Schematic for commissioning test: real-time operation.




π)100

#### **Commissioning Test: P Control**



PCC active power step from 25 to 35 MW, without limitations.




*PCC active power step from 14 to 19 MW, with boiler limitations.* <sup>29</sup> π.)100

### **Commissioning Test: Q Control**




PCC reactive power step from 0 to Qmax.




PCC reactive power step from 0 to Qmin.

π)100

#### **Commissioning Test: U Control**





PCC voltage step from 121 to 119 kV.

### Conclusions

Πυ>100

#### • Positive outcomes:

- After approval by the TSO, the control system was installed as is in the power plant;
- Control system has been in operation for 2 years without any problems;
- Significant cost savings for the power plant owner.

### Conclusions

Πυ>100

#### Challenges faced:

- Convincing other parties that real-time simulation is a suitable platform for development and commissioning testing;
- Missing double point information feature;
- Simulation reliability of IEC-104 protocol.

TALLINN UNIVERSITY OF TECHNOLOGY Ehitajate street 5, 19086 Tallinn, Estonia Phone +372 620 2002 (Mon-Fri 8.30 AM – 5.00 PM) Tanel.Sarnet@taltech.ee

TU>100